

- AS IT IS USED TO GIVE ADEQUATE AND UNINTERRUPTED SERVICE ONLY DURING TEST OR REPAIR OF THE METER.
- 2. IF THE BY-PASS IS TO BE INSTALLED ABOVE THE METER, THE MINIMUM CLEARANCE REQUIRED FROM THE TOP OF THE METER TO THE BOTTOM OF THE BY-PASS IS 800 mm.
- 3. REQUEST DELIVERY OF THE NEPTUNE METER FOR THE SAME TIME THE PIPING IS TO BE INSTALLED.
- 4. MINIMUM CLEARANCE FROM WALL IS 300 mm.
- 5. NO SOLDERED JOINT IS PERMITTED ON THE STREET SIDE OF THE MAIN SHUT-OFF.
- 6. CONTRACTOR SHALL HAVE METER INSTALLED BY A LICENSED PLUMBER.
- 7. OPERATIONS METER SHOP IS TO BE CONTACTED FOR FINAL INSPECTION ONCE INSTALLATION IS COMPLETE.
- 8. BY-PASS VALVE TO BE TAGGED AND SEALED FOLLOWING FINAL INSPECTION.
- 9. 40 OR 50 mm N.P.T. MALE x 63.5 mm C.S.A. FEMALE (BRASS ONLY) SWIVEL SUITED FOR STANDARD 63.5 mm MALE END PUMPER HOSE CONNECTION.
- 10. 63.5 mm BRASS PLUG.
- 11. ALL DIMENSIONS ARE IN MILLIMETRES UNLESS OTHERWISE SHOWN.



## DETAIL OF 40 OR 50 mm WATER METER INSTALLATION

DRAWN BY: LRC/STS/RF	REV No: 1
DATE: 2003-03-03	REV DATE: 2012-02-01
SCALE: NTS	CAD/FILE No.: A1981-1 (1 OF 1)
APP'D:	GSSD-1107.010