

NOTES

- 1. ALL CONCRETE TO BE 20 MPa COMPRESSIVE STRENGTH AT 28 DAYS.
- 2. FRAME & COVER TO BE THAT SUPPLIED BY KONDU MFG. CO. LTD. PRESTON, ONT; OR EQUAL.
- 3. CONCRETE HANDHOLE SHOULD BE ORDERED WITH 2, 3, OR 4 OPENINGS AS REQUIRED.
- 4. A SEALANT ACCEPTABLE TO THE ENGINEER SHALL BE UTILIZED TO PROVIDE A WATERPROOF SEAL BETWEEN DUCTS AND HANDHOLE STRUCTURE.
- 5. ALL DIMENSIONS ARE IN MILLIMETRES UNLESS OTHERWISE SHOWN.
- 6. OPENINGS NOT USED ARE TO BE PLUGGED TO PREVENT EARTH INFILTRATION.
- 7. GRANULAR 'A' AND 19 mm CRUSHED STONE TO BE WELL COMPACTED.



PRECAST CONCRETE HANDHOLE FOR TRAFFIC SIGNAL DUCTS

DRAWN BY: STS/RFRANK	REV No:
DATE: 2003-03-03	REV DATE:
SCALE: NTS	CAD/FILE No.:
	A1928-1 (1 OF 1)
APP'D:	GSSD-1228.010