



2023

LESSONS LEARNED

LUCIANO VALLE

MANAGER OF CONSTRUCTION SERVICES

EQUIPMENT TRAVELLING OUTSIDE OF CONSTRUCTION ZONE

Abide by the following:

- By-law 2011-219 – The Fouling, Obstruction, Use and Care of Roads Specifically Sub-Section 16 – Vehicles with Cleats etc.
- O.Reg 398/16 Road-Building Machines Specifically Sub-Section 3 -Prohibition of loads



QUALITY CONTROL EXPECTATIONS

- GSSS 501 Construction Specification for Compaction
 - Granular and soils shall be compacted according to Method A and according to the field compaction specified in Table 1.
- GSSS 501.07.04.02.03 Submission of Test Data
 - Test result data to be provided within 1 (one) business day.
 - Reported on the Field Compaction Report form in Appendix B or another approved form which shall be signed and submitted to the City.
- Send results to Constructionservices_QA@greatersudbury.ca



GRANULAR TICKETS

- Ticket requirements as per GSSS 102.07.01.01
- Weigh Tickets are to be submitted to the Inspector on site.
Will not be accepted beyond the day they were delivered to site.



TRENCH SAFETY

- Ontario Health and Safety Act
Regulation 213/91 section 234
- Ensure employees have proper training
and a full understanding of Trench Safety





QUESTIONS?

